

Sizes.tex

13 February 2026

14:52

Contents

1	Sizes of Wire Gauges from Sizes.com	3
1.1	Wire gauges	3
1.2	Conversions between wire gauges	4
1.3	Misc Gauges	4
1.4	American or Brown & Sharp Wire Gauge from Sizes.com	6
1.4.1	Wire Size Problems	6
1.4.2	American Wire Gauge	7
1.4.3	Inch version of American or Brown & Sharp Wire Gauge from Sizes.com	7
1.4.4	Metric version of American or Brown & Sharp Wire Gauge from Sizes.com	9
1.5	Birmingham Wire Gauge	11
1.5.1	C. Holtzapffe's Gauge values	12
1.5.2	Latimer Clark's gauge values	13
1.5.3	R. S. Culley's Gauge values	13
1.5.4	Notes for the Birmingham Wire Gauge Table	15
1.5.5	Sources	15
1.5.6	For further reading	17
1.6	French wire gauges	19
1.6.1	Sources for French wire gauges	19
1.6.2	Jauge de Paris 1857	20
1.6.3	Correspondence Between Paris Gauge and Wire Diameter	21
1.6.4	Jauge Japy	23
1.6.5	Jauge de Limoges	25
1.6.6	Jauge Carcasse or du Commerce	27
1.6.7	Sources for French wire gauges	29
1.7	Metric Wire Sizes	30
1.7.1	Metrically-sized equivalents for SWG-sized electrical cables	30
1.7.2	Metric-sized equivalents for AWG-sized electrical cables	32
1.8	Making Wire	33
A	A table comparing diameters of some common gauges	35
A.1	American or Brown & Sharpe Wire Gauge	39
A.2	Birmingham or Stubs' Iron Wire	41
A.3	Stubs' Steel Wire Gauge	43
A.4	Washburn & Moen, Roebling or American Steel and Wire Co.	45
A.5	Imperial Wire Gauge	47
A.6	Whitworth's	49
A.7	Steel Wire Gauge, Waterbury Co., 1917	51
A.8	Sizes of Numbers of the United States Standard Gauge	53
B	Privacy Statement from Sizes.com	55

List of Tables

1	Inch version of American or Brown & Sharp Wire Gauge	8
2	Metric version of American or Brown & Sharp Wire Gauge	10
4	Birmingham or Stubs' Wire Gauge	11
5	Birmingham or Stubs' Wire Gauge from C. Holtzapffel	12
6	Birmingham or Stubs' Wire Gauge from Latimer Clark	13
7	Birmingham or Stubs' Wire Gauge from R. S. Culley	13
8	Jauge de Paris 1857	20
9	Jauge Japy	23
10	Jauge de Limoges	25
11	Jauge de Limoges	27
12	Metrically-sized equivalents for SWG	31
13	Metric-sized equivalents for AWG	32
14	Comparing Diameters of some Common Gauges	38
15	American or Brown & Sharpe Wire Gauge	39
16	Birmingham or Stubs' Iron Wire Gauge	41
17	Stubs' Steel Wire Gauge	43
18	Washburn & Moen, Roebling or American Steel and Wire Co. Gauge	45
19	Imperial Wire Gauge	47
20	Whitworth's Gauge	49
21	Steel Wire Gauge, Waterbury Co., 1917	51
22	United States Standard Gage	53

List of Figures

1	Birmingham or Stubs' Wire Gauge from C. Holtzapffel, Latimer Clark and R.S.Cully BWG.inc	14
2	Jauge de Paris 1857 FWS.inc	21
3	Jauge Japy FWS.inc	24
4	Jauge de Limoges FWS.inc	26
5	Jauge carcasse or du Commerce FWS.inc	28
6	American or Brown & Sharpe Wire Gauge Common Gauges.inc	40
7	Birmingham or Stubs' Iron Wire Gauge Common Gauges.inc	42
8	Stubs' Steel Wire Gauge Common Gauges.inc	44
9	Washburn & Moen, Roebling or American Steel and Wire Co. Gauge Common Gauges.inc	46
10	Imperial Wire Gauge Common Gauges.inc	48
11	Whitworth's Gauge Common Gauges.inc	50
12	Steel Wire Gauge, Waterbury Co., 1917 Gauge Common Gauges.inc	52
13	American Standard Gauge for Sheet and Plate Iron and Steel BandSamericanstandard.inc	54

1 Sizes of Wire Gauges from Sizes.com

Source: [Sizes.com](https://www.sizes.com)'s web site for "Wire Gauges" with my additions.

The way wire is made leads to a "natural" series of sizes. A rod (made in a rolling mill) is pulled through a hole whose diameter is slightly smaller than the rod's. This process is repeated through ever-smaller holes until the wire is as fine as desired.

To reduce the number of steps for economy's sake, the manufacturer would like the change in size at each drawing to be as large as possible. On the other hand if the change in size is too great the wire will break while being drawn. Older wire gauges like the Birmingham, Washburn & Moen, and Lancashire came from calling the wire from the first drawing number 1, from the second drawing #2, and so on. Note that the higher the number, the finer the wire.

For a description of how wire is made see [subsection 1.8](#), page 33 for an explanation from Hugh P. Tiemann.

It is impossible to draw a wire to an exact size. Ordinary practice is to draw a No. 10 B. & S. wire between 101 and 103 mils. The resulting wire may average 102 or 101.9 mils, or something different from either. A table calculated on the exact size is, therefore, as nearly right as though ordinary shop sizes were used. The weight and resistance of an actual wire will very seldom correspond with any table.

Wire in Electrical Construction. Trenton, NJ:
John A. Roebling's Sons Company, 1916, Page 75.

The web site [Sizes.com](https://www.sizes.com) has information about many things. One of them is the sizes of wire. I copied their information and reformatted it and have it here. Their information is quite interesting and I recommend their site as having large amount of useful data.

On their web page there is a button to select "materials index" which is recommended.

1.1 Wire gauges

On their Wire Gauges page the following different wire gauges are listed:

- Table Comparing Common Gauges Sizes [subsection A.8](#), page 53
- American Steel and Wire Gauge [section 1.3](#), page 5
- American Wire Gauge (AWG) [subsubsection 1.4.2](#), page 7
- Birmingham, Stubs' Iron Wire Gauge [subsection 1.5](#), page 11
- British Standard Wire Gage ??, page ??
- Brown & Sharpe Wire Gauge (AWG) [subsection 1.4](#), page 6
- French Wire gauges [subsection 1.6](#), page 19 (This is the original version from [Sizes.com](https://www.sizes.com).
 - Gauge Carcasse [section 1.6.6](#), page 28
 - Gauge de Limoges [subsubsection 1.6.5](#), page 25
 - Gauge de Paris [subsubsection 1.6.2](#), page 20

⁰Full Table.inc 13 February 2026 14:52

- Jauge Japy [subsection 1.6.4](#), page 23
- London Gauge [section 1.3](#), page 4
- Market Wire Gauge [section 1.3](#), page 5
- Miscellaneous Gauges [subsection 1.3](#), page 4
 - Edison Standard Wire Gauge [section 1.3](#), page 4
 - Morse Twist Drill Gauge [section 1.3](#), page 4
 - Old English Wire Gauge [section 1.3](#), page 4
 - Roebling Wire Gauge [section 1.3](#), page 5
 - Steel Wire Gauge [section 1.3](#), page 5
 - Whitworth's Wire Gauge [section 1.3](#), page 5
- United States Standard Gauge [subsection A.8](#), page 53
- Washburn & Moen Wire Gauge [section 1.3](#), page 5

1.2 Conversions between wire gauges

On their Wire Gauges page the following different wire gauge conversions are listed:.

- American Wire Gauge to ISO metric sizes
- ISO metric sizes to American Wire Gauge [Table 13](#), page 32
- British Standard Wire Gauge to ISO metric sizes [subsection 1.7.1](#), page 30 [Table 12](#), page 31
- ISO metric sizes to British Standard Wire Gauge [subsection 1.7.1](#), page 30

1.3 Misc Gauges

Edison Standard wire gauge A standard used in the 19th century by the Edison Electrical Light Company for wires made to carry electric current. The gauge number is the number of thousands of circular mils in the wire's cross section. Cross-sectional area is much more reasonable than diameter as a basis for sizing electric conductors.

Morse Twist Drill gauge It is a copy of the Lancashire gauge, the sizes being taken from wire and rod imported from Britain.

Old English wire gage Also known as the London gage. 19th century. Used for brass and copper wire, especially brass wire for weaving.

Roebling wire gauge Use began about 1830. Originally named for the Washburn and Moen Manufacturing Company, which was later merged into the American Steel and Wire Co.

This is the same as the Washburn and Moen Gauge, or the American Steel and Wire Gauge, except the diameters in most cases are given to the nearest mil.

This gauge is so generally used for steel wire that it is sometimes called the Steel Wire Gauge or the Market Wire Gauge.

A plot of this gauge is shown at [Table 14](#), page 46.

Wire in Electrical Construction.

Trenton, NJ:

A. Roebling's Sons Company, 1916, Page 51.

Stub's Steel Wire gauge Used for drill rod and tool steel wire. It is the basis of, though not identical to, the numbered sizes of American Standard twist drills. Note that there is also a Stub's Iron Wire Gauge.

A plot of this gauge is shown at [Table 14](#), page 44.

Whitworth's wire gauge Also known as Cocker's Wire Gauge. The gauge number is simply the diameter of the wire in thousandths of an inch. For example, #1 has a diameter of 0.001 inch.

A plot of this gauge is shown at [Table 14](#), page 50.

1.4 American or Brown & Sharp Wire Gauge from Sizes.com

Source: [Sizes.com](http://www.sizes.com)'s web site.

The first effort toward uniformity was made by the wire manufacturers around Birmingham, England, who adopted a set of gauge numbers called the "Old English Wire-gauge," which was subsequently changed to the Birmingham Wire-gauge. This Birmingham wire-gauge formed the basis for most of the gauge numbers adopted by the American wire manufacturers with certain minor changes introduced by individual manufacturers, and up to the year 1857 this system continued with its consequent confusion and variations of size. During that year the Association of Brass Wire and Sheet Manufacturers requested the firm of Brown & Sharpe to make a number of "V" gauges numbered according to the Birmingham system, which they intended to adopt as their standard. In constructing this gauge it was at once seen by the Brown & Sharpe Company that there was a great lack of uniformity in the variations between the different sizes and numbers used in this system, and consequently Brown & Sharpe recommended to the association that they adopt a gauge the numbers of which would correspond to areas varying in geometrical progression. The advantage of such a system was at once seen by the brass manufacturers, and the gauge then proposed was adopted by them. Since that time the wisdom of the change has been proved throughout its continued use, especially for the users of electrical conductors, in which service the carrying capacity of the wire varying as the area is the most important point to be determined.

Source:

Author: Frederick A. C. Perrine.

Title: Conductors for Electrical Distribution. Their Materials and Manufacture.

Publisher: New York: D. Van Nostrand Co., 1903

Page: 76-77.

1.4.1 Wire Size Problems

With the exception of No. 0000, which is 460 mils in diameter, and No. 36 which is 5 mils, the diameters of the sizes B. & S. G. are indeterminate. The ratio of the diameter of any one size to that of the next lower size is $.890\ 525\ 718\ 5$. Using this ratio and deriving the size of each number from the next greater finally gives us $5.000\ 000\ 02$ mils as the diameter of a No. 36 instead of an even 5 mils. The ratio is, therefore, slightly too large.

Title: Wire in Electrical Construction.

Publication: Trenton, NJ

Author: John A. Roebling's Sons Company, 1916

Page: 51.

Source: WWW.Sizes.com/materl1sSaw Size

1.4.2 American Wire Gauge

Also called the American Wire Gauge (AWG). Used in the United States since at least the 1880s for wires in all metals except iron and steel. There are two defined sizes: number 0000 wire is 0.4600 inch in diameter and number 36 is 0.0050 inch. The diameters of intermediate numbers are found by subdividing the interval between those sizes into 39 geometrical steps, with a constant ratio between adjacent sizes of:

To calculate the diameter of an American Wire Wire using the gauge number:

$$d = 0.005 \times 92^{\frac{36 - \text{Gauge}}{39}}$$

The relationship between AWG wire sizes is: the 39th root of the fraction 0.4600 over 0.0050 equals 1.1229322

The diameter of each succeeding smaller size is the reciprocal, 0.890525 times the diameter of the previous, larger, size.

Reference: ASTM Standard B 258-02, Standard specification for standard nominal diameters and cross-sectional areas of AWG sizes of solid round wires used as electrical conductors.

1.4.3 Inch version of American or Brown & Sharp Wire Gauge from Sizes.com

Gauge (AWG)	Diameter mils	Area circular mils	Resistance in ohms, 20°C per 1000 feet	Weight 1000 feet, in lbs.
0 000	460.0	211,600	.0490	640.5
000	409.6	167,806	.0618	507.9
00	364.8	133,077	.0779	402.8
0	324.9	105,535	.0983	319.5
1	289.3	83,692.7	.1239	253.3
2	257.6	66,371.3	.1563	200.9
3	229.4	52,634.3	.1970	159.3
4	204.3	41,741.3	.2485	126.4
5	181.9	33,102.4	.3133	100.2
6	162.0	26,251.4	.3951	79.46
7	144.3	20,818.3	.4982	63.02
8	128.5	16,509.7	.6282	49.97
9	114.4	13,092.8	.7921	39.63
10	101.9	10,383.0	.9989	31.43
11	90.74	8,234.11	1.260	24.92
12	80.81	6,529.95	1.588	19.77
13	71.96	5,178.48	2.003	15.68
14	64.08	4,106.72	2.525	12.43
15	57.07	3,256.78	3.184	9.858
16	50.82	2,582.74	4.016	7.818
17	45.26	2,048.21	5.064	6.200
18	40.30	1,624.30	6.385	4.917
19	35.89	1,288.13	8.051	3.899
20	31.96	1,021.53	10.15	3.092
<i>Continued on the next page.</i>				

<i>Continued from the previous page.</i>				
Gauge (AWG)	Diameter mils	Area circular mils	Resistance in ohms, 20°C per 1000 feet	Weight 1000 feet, in lbs.
21	28.46	810.114	12.80	2.452
22	25.35	642.450	16.14	1.945
23	22.57	509.486	20.36	1.542
24	20.10	404.041	25.67	1.223
25	17.90	320.419	32.37	.9699
26	15.94	254.104	40.81	.7692
27	14.20	201.513	51.47	.6100
28	12.64	159.807	64.90	.4837
29	11.26	126.733	81.84	.3836
30	10.03	100.504	103.2	.3042
31	8.928	79.7031	130.1	.2413
32	7.950	63.2075	164.1	.1913
33	7.080	50.1258	206.9	.1517
34	6.305	39.7516	260.9	.1203
35	5.615	31.5244	329.0	.0954
36	5.000	25.0000	414.8	.0757
37	4.453	19.8259	523.1	.0600
38	3.965	15.7227	659.6	.0476
39	3.531	12.4686	834.8	.0377
40	3.145	9.88807	1049.0	.0299

Table 1: Inch version of American or Brown & Sharp Wire Gauge

A plot of this gauge is shown at [Table 14](#), page 40.

1.4.4 Metric version of American or Brown & Sharp Wire Gauge from Sizes.com

Gauge (AWG)	Diameter mils	Area circular mils	Resistance in ohms, 20°C per 1000 feet	Weight 1000 feet, in lbs.
0 000	11.68	107.2	.1608	953.2
000	10.40	85.03	.2028	755.9
00	9.266	67.43	.2557	599.5
0	8.252	53.48	.3224	475.4
1	7.348	42.41	.4066	377.0
2	6.544	33.63	.5127	299.0
3	5.827	26.67	.6465	237.1
4	5.189	21.15	.8152	188.0
5	4.621	16.77	1.028	149.1
6	4.115	13.30	1.296	118.3
7	3.665	10.55	1.634	93.78
8	3.264	8.366	2.061	74.37
9	2.906	6.634	2.599	58.98
10	2.588	5.261	3.277	46.77
11	2.305	4.172	4.132	37.09
12	2.053	3.309	5.211	29.42
13	1.828	2.624	6.571	23.33
14	1.628	2.081	8.285	18.50
15	1.450	1.650	10.45	14.67
16	1.291	1.309	13.17	11.63
17	1.150	1.038	16.61	9.226
18	1.024	.8231	20.95	7.317
19	.9116	.6527	26.42	5.803
20	.8118	.5176	33.31	4.602
21	.7230	.4105	42.00	3.649
22	.6438	.3255	52.96	2.894
23	.5733	.2582	66.79	2.295
24	.5106	.2047	84.21	1.820
25	.4547	.1624	106.2	1.443
26	.4049	.1288	133.9	1.145
27	.3606	.1021	168.9	.9077
28	.3211	.08098	212.9	.7199
29	.2589	.06422	268.5	.5709
30	.2546	.05093	338.6	.4527
31	.2268	.04093	426.9	.3590
32	.2019	.03203	538.3	.2847
33	.1798	.02540	678.8	.2258
34	.1601	.02014	856.0	.1791
35	.1426	.01597	1079.4	.1420
Continued on the next page.				

<i>Continued from the previous page.</i>				
Gauge (AWG)	Diameter mils	Area circular mils	Resistance in ohms, 20°C per 1000 feet	Weight 1000 feet, in lbs.
36	.1270	.01267	1361.0	.1126
37	.1131	.01005	1716.2	.0893
38	.1007	.00797	2164.1	.0708
39	.0897	.00632	2728.9	.0562
40	.0799	.00501	3441.1	.0445

Table 2: Metric version of American or Brown & Sharp Wire Gauge

1.5 Birmingham Wire Gauge

Source: [Sizes.com](https://www.sizes.com)'s web site.

The steps are irregular. Departmental sanction by the United States government ended in 1914.

Gauge	Diameter in inches				Gauge	Diameter in inches			
	1	2	3	4		1	2	3	4
0 000		0.454			17		0.058	0.058	0.057
000		0.425			18		0.049	0.049	0.050
00		0.380		0.363	19		0.042	0.042	0.045
0		0.340		0.331	20		0.035		0.040
1		0.300	0.300	0.300	21		0.032		0.035
2		0.284	0.280	0.280	22		0.028		0.030
3		0.259	0.260	0.260	23		0.025		
4		0.238	0.240	0.240	24		0.022		
5		0.220	0.220	0.220	25		0.020		
6		0.203	0.200	0.200	26		0.018		
7		0.180	0.185	0.185	27		0.016		
8		0.165	0.170	0.170	28		0.014		
9		0.148	0.155	0.155	29		0.013		
10		0.134	0.140	0.140	30		0.012		
11		0.120	0.125	0.125	31		0.010		
12		0.109	0.110	0.110	32		0.009		
13		0.095	0.095	0.095	33		0.008		
14		0.083	0.085	0.085	34		0.007		
15		0.072	0.075	0.075	35		0.005		
16		0.065	0.065	0.065	36		0.004		

Table 4: Birmingham or Stubs' Wire Gauge

A plot of this gauge is shown at [Table 14](#), page 42.

1.5.1 C. Holtzapffe's Gauge values

Gauge	Diameter in inches	Gauge	Diameter in inches
0 000	0.454	17	0.058
000	0.425	18	0.049
00	0.380	19	0.042
0	0.340	20	0.035
1	0.300	21	0.032
2	0.284	22	0.028
3	0.259	23	0.025
4	0.238	24	0.022
5	0.220	25	0.020
6	0.203	26	0.018
7	0.180	27	0.016
8	0.165	28	0.014
9	0.148	29	0.013
10	0.134	30	0.012
11	0.120	31	0.010
12	0.109	32	0.009
13	0.095	33	0.008
14	0.083	34	0.007
15	0.072	35	0.005
16	0.065	36	0.004

Table 5: Birmingham or Stubs' Wire Gauge from C. Holtzapffel

1.5.2 Latimer Clark's gauge values

Gauge	Diameter in inches	Gauge	Diameter in inches
1	0.300	11	0.125
2	0.280	12	0.110
3	0.260	13	0.095
4	0.240	14	0.085
5	0.220	15	0.075
6	0.200	16	0.065
7	0.185	17	0.058
8	0.170	18	0.049
9	0.155	19	0.042
10	0.140		

Table 6: Birmingham or Stubs' Wire Gauge from Latimer Clark

1.5.3 R. S. Culley's Gauge values

Gauge	Diameter in inches	Gauge	Diameter in inches
00	0.363	11	0.125
0	0.331	12	0.110
1	0.300	13	0.095
2	0.280	14	0.085
3	0.260	15	0.075
4	0.240	16	0.065
5	0.220	17	0.057
6	0.200	18	0.050
7	0.185	19	0.045
8	0.170	20	0.040
9	0.155	21	0.035
10	0.140	22	0.030

Table 7: Birmingham or Stubs' Wire Gauge from R. S. Culley

The three values from Birmingham or Stubs' Wire Gauge above differ slightly. Here all three are plotted together.

Plot of Steel Wire Gauge, Waterbury Co., 1917 Gauge




Figure 1: Birmingham or Stubs' Wire Gauge from C. Holtzapffel, Latimer Clark and R.S.Cully BWG.inc

1.5.4 Notes for the Birmingham Wire Gauge Table

1. This column is reserved for a yet-to-be-discovered 18th century list of BWG values.

2. C. Holtzapffel.

On the Gauges at present used, for measuring the thickness of sheet metals and wires, and proposals for a new system of Gauges, founded on the decimal subdivision of the Standard Inch.

Journal of the Franklin Institute: , vol 15, August, 1847.

Reprinted from the: Glasgow Practical Mechanic and Engineers' Magazine:, circa 1843.

Holtzapffel's decimal figures are reprinted, with acknowledgement in, for example,

Joshua Rose: Modern Machine-Shop Practice, vol 1, 2nd ed.,

New York: Charles Scribner's Sons, 1892. page 384.

and, without acknowledgement, in, for example,

(U.S.) Dept. of Commerce and Labor.: Circular of the Bureau of Standards. No. 31. Copper Wire Tables.

Washington: Government Printing Office, 1912, Page 35, in a column headed "Birmingham Wire Gauge (Stubs')", Roebling (source 6 below) also identifies the B.W.G. with Stubs' Iron Wire Gauge, but whatever the situation in the early 1900s, at an earlier date the Birmingham Wire Gauges were not identical with Stubs'. The values given in Roebling's book (page 52) are those of Holtzapffel.

3. Latimer Clark

4. R. S. Culley.: A Handbook of Practical Telegraphy. 3rd ed. rev and enlarged.

London: Longmans, Green, Reader and Dyer, 1868, Page 296.

An authoritative source that went through many editions and was adopted by, for example, the Department of Telegraphs for India. But see source note 1, below.

1.5.5 Sources

1. Birmingham Wire Gauge — The diameters of the several gauges must be considered approximate only. There is no authorised standard, and the sizes of different makers vary considerably.

A Handbook of Practical Telegraphy. 3rd ed. rev and enlarged.

London: Longmans, Green, Reader and Dyer, 1868, Page 296

2. STANDARD GOVERNMENT WIRE

1st.— The wire supplied under this tender must be of the gauge known as No. 6, Birmingham Wire Gauge (diameter .170 of an inch.)

Advertisement by Charles T. Chester,

Telegraph Wire.

The Telegrapher, vol 8, no, 21, Jan 13, 1871,. Page 166.

The advertisement ran every week, identically worded, so a typographical error is unlikely. The advertiser, Charles T. Chester, was regarded as one of the two best manufacturers of iron telegraph wire in the United States. Note that in Holtzapffel's list, No. 6 is 0.203 of an inch, not 0.170. Chester appears to be quoting a U.S. government specification.

3. In purchasing iron wire it has hitherto been the invariable custom to specify its size according to the Birmingham Gauge. This wire gauge varies with every manufacturer, and there is not only no standard from which he can correct his own, but no one is aware on what basis the gauge was originally made, so that it is impossible to reproduce it in any correct shape. Mr. Culley, in a note to table (No. 9) in his hand-book, says, "Birmingham Wire Gauge. — The diameters of the several gauges must be considered approximate only. There is no authorized standard, and the sizes of different makers vary considerably."

Mr. Latimer Clark's paper, read before the British Association in September, 1867, so well describes the variations of different makers that it is useless to bring forth any further proof of its inconsistency and its self-evident inconvenience. It is evident that, in establishing any gauge, it should have been coherent through out; it should have been based on a regular increasing series, and should have started from some recognized and well known unit. Mr. Latimer Clark has pointed out the probability that the present Birmingham Wire Gauge originated from No. 16 Bell Wire as unit, that wire being 1/16th of an inch in diameter; but this is a mere arbitrary size to select, and although it may be understood that before telegraphs were in existence bell-hangers would start from a size most convenient to them, that size bears no relation to any telegraphic purpose, and it bears no relation whatever to the remainder of the series.

H. Mallock and W. H. Preece.

On a New Telegraph Wire Gauge.

Telegrapher, vol 8, no 61, 19 October 1871. Page 481.

4. This gauge (hereinafter referred to as the B.W.G.) is represented by a series of numbered slots or cuts on the edges of a small rectangular steel plate. It is the practice to distinguish the diameters of wires and the thickness of plates of metal by the number of the slot or cut which the wire or plate may fit.

There is no standard of such gauge or common agreement amongst those interested as to what are the dimensions in parts of an inch of the several slots or sizes of the true B.W.G. Its sizes are not geometrically or arithmetically progressive, and, consequently, bear no definite relation to each other. Its origin is obscure, and it would appear that the several slots or sizes arose from time to time as a new wire or new plate was introduced, and as the exigencies of a particular trade demanded. Considerable annoyance to engineers and pecuniary loss to contractors is stated to occur from a want of accuracy in the copies of this gauge, and the necessity of establishing a standard has lately been discussed, both in this country and in the United States.

Board of Trade.

12th Annual Report to Parliament on Standard Weights and Measures, for 1877-78.

5. When Britain adopted the Imperial Wire Gauge in 1884, the manufacturers of sheet metal rebelled. Though formerly they and the wire makers had used a common gauge, the new gauge suited the needs of wire makers, but not of sheet metal workers. In December the iron manufacturers met and resolved to adopt the Birmingham wire gauge as the standard gauge for sheet metal.

There has been a great deal of discussion among the iron men, and two days ago a very influential meeting was held at the Birmingham Exchange, at which nearly every large sheet-metal works in the district was represented.

It was there stated that the decision arrived at at the meeting in December had not been satisfactory, because manufacturers had not after long and serious discussion been able to agree since then as to what the Birmingham wire-gauge really has been and is.

The result is a serious dilemma. The new Imperial Wire Gauge is only adapted for the use of wire-makers, and the old Birmingham Gauge is a doubtful, some even said mythical, standard. One party declared it was really Partridge's gauge and another that it was Stubs's gauge, and the result has been confusion, the meeting unanimously resolved:

That this meeting adopts the gauge known as the Birmingham Gauge, and further resolves that such Birmingham Gauge shall be the proposed standard gauge for sheet-iron and hoop-iron already printed and issued by the South Staffordshire Ironmasters' Association to the manufactured-iron trade, and by them approved, and also deposited with the Board of Trade, and that such gauge shall in future be used under the initial letters "B. G." This new gauge, to be known hereafter as "B. G.," is described as being a symmetrical adjustment of the Birmingham Wire Gauge known as "B.W.G.," formulated by Mr. Hatton at the request of the Iron Masters' Association.

Wilson King,
Second Wire Gauge Report.
United States Consular Reports, No. 39 — March 1884.
Washington: Department of State., Page 316.

6. There are several other gauges in use, such as Wynn's, Cocker's Ryland's Watkins', Robinson's, and Brown and Sharpe's American Gauge, while a great number are also employed under the name of "the old Birmingham Wire Gauge," and other titles.

A table attached to Mr. L. Clark's paper gives the diameter of each number of Birmingham Wire Gauge in decimals of an inch, according to thirteen published lists by different authorities, all of which differ.

There can be little doubt that reform in this matter is very greatly required. For a long time it has been the custom in specifying the size of the wires for submarine cables to state, besides the number of the Birmingham Wire Gauge, the decimals of an inch that shall be understood by that number. This has been found necessary on account of the vagueness of the meaning of the words "Birmingham Wire Gauge," owing to the number of different interpretations of these words which have grown up through different manufacturers of gauges making them on some arbitrary principle of their own; the principle on which the original B.W.G. was constructed, if it ever had any, having been lost in obscurity possibly by bad workmanship in some of the early gauges.

Review of Report of the Committee of the Society of Telegraph Engineers on the Birmingham
Wire Gauge
Engineering, vol 29, Feb 20 1890. Page 141.

7. This is abbreviated B.W.G. It is the same as Stubs' Iron Wire Gauge, but entirely different from Stubs' Steel Wire Gauge. Galvanized Telegraph and Telephone Wire, both bare and insulated, and Galvanized Armor Wire are usually designated by this gauge. Its use is not very extensive and is becoming less.

Wire in Electrical Construction.
Trenton, NJ: John A. Roebling's Sons Company, 1916, Page 51.

1.5.6 For further reading

- Thomas Hughes
The English Wire Gauge, with Descriptive Tables and Drawings
London: Spon & Co., October, 1879

- Committee:

Report to the Council of the Society of Telegraph Engineers on the Birmingham Wire Gauge.
Journal of the Society of Telegraph Engineers, vol 8, pages 476-504, 1879

A full discussion of the situation. In at least some copies, bound at the end of the volume is a second copy of the report, followed by “On the Unit of the Birmingham Wire Gauge”, by C.V. Walker, a discussion of that paper, and finally Latimer Clark’s, 1867 paper, “On the Birmingham Wire Gauge”.

1.6 French wire gauges

Source: [Sizes.com](https://www.sizes.com)'s web site.

In addition to France, these gauges were used in Spain, Italy, Switzerland, Greece, Asia Minor, South America, and even to an extent in Germany, usually in competition with other gauges. They were used for wire and wire nails in the 19th and early 20th centuries.

1.6.1 Sources for French wire gauges

There is no doubt but that English wire gauges have been largely used on the continent of Europe in former times, and especially the so-called Birmingham wire-gauge. At present this wire gauge is still used in Belgium, Russia, Sweden, Norway, and Denmark. The new standard gauge is only being introduced by degrees. In Germany, the Birmingham wire gauge was used up to the year 1878, although the ancient Westphalian wire gauge and also the French gauge (or *jauge de Paris*) were used besides, to a small extent. In 1872, the German wire drawers adopted the so-called millimetre wire gauge, which is at present used throughout Germany and Austria, other wire gauges only being used occasionally. The millimetre gauge indicates the size of wire by tenths of a millimetre, so that for instance the No. 42 wire would be 4.2 mm. thick, and No. 4 wire would be 0.4 mm. thick. Certain standard sizes are, however, adopted by preference, coming up very nearly to the old Birmingham wire gauge, say:

As regards the system of measurement employed in Germany, wire gauges, i.e., plates of steel with notches representing the various sizes of wire, are still much used in the works, but in addition the micrometer or screw gauge is much employed, allowing the measurement of the size of wire to the smallest fraction of a millimetre.

In France, Spain, Italy, Switzerland, Greece, and Asia Minor, the French gauge, and principally the so-called *jauge de Paris* of 1857, is used. This gauge indicates the size of wire by numbers having certain equivalents in millimetres; and, contrary to the Birmingham wire gauge, where the smallest number indicates the largest size, in the French gauge the smallest number indicates the smallest size.

The *jauge "japy"*, similar to the *jauge de Paris*, but with slightly smaller sizes for the different numbers, is also used to some extent in France and Switzerland; for the finer wires, card wire, copper wire, etc., the so-called *jauge "carcasse"* is in use.

With regard to Great Britain and the British colonies, they all now use the new standard wire gauge. In the United States of America, hitherto the Stubbs' Birmingham wire gauge has, we believe, been mostly used, besides Washburn & Moen's, and Brown and Sharpe's wire gauges.

If we are not mistaken there is a tendency in the United States to the adoption of the millimetre gauge. If this gauge should really be adopted in the states, the Americans will show that they are readier to take up an improvement than their English cousins, the millimetre gauge having been frequently proposed in England, but always declined on account of the conservative opposition it encountered. In South America both the Birmingham wire gauge or the new standard gauge and the *jauge de Paris* are used according to whether buyers have been accustomed to purchase in England or in France, the French imports of wire having of late been replaced by imports from Germany.

We are used to sell in the export market to whatever gauge may be desired.

In concluding, we beg to give you our opinion that the best system of measuring is the millimetre gauge, and that this gauge will be used to greater extent in the future; this will, however, greatly depend upon whether England will do away with her ancient system of measures, weights and money, and replace it by the far simpler metric system. This, we believe, is only a question of time.

A letter from Felten & Guillaume, of Müllheim, near Cologne, "the largest makers in the world of iron and steel telegraph wire" replying to an inquiry from a M. Welles, who submitted it to *The Electrical World*.

It subsequently appeared in *The Electrician and Electrical Engineer*, vol. 5, page 476 (Dec. 1885). Welles commented that “the statements made as to usage in different countries refer to line wire, and not to sheet metal, fine copper wires, etc.”

1.6.2 Jauge de Paris 1857

Gauge	Diameter in Millimeters	Gauge	Diameter in Millimeters
P15	0.15	8	1.30
P14	0.16	9	1.40
P13	0.17	10	1.5
P12	0.18	11	1.6
P11	0.20	12	1.8
P10	0.22	13	2.0
P9	0.23	14	2.2
P8	0.25	15	2.4
P7	0.27	16	2.7
P6	0.28	17	3.0
P5	0.30 (Some say 0.3100)	18	3.4
P4	0.34	19	3.9
P3	0.37 (Some say 0.3810)	20	4.4
P2 or PP	0.42	21	4.9
P1	0.46	22	5.4
P0 or P	0.50	23	5.9
1	0.60	24	6.4
2	0.70	25	7.0
3	0.80	26	7.6
4	0.90	27	8.2
5	1.00	28	8.8
6	1.10	29	9.4
7	1.20	30	10.0

Table 8: Jauge de Paris 1857

Source

Cl. de Laharpe.
Notes & Formules de L'Ingénieur et du Constructeur-Mécanicien.
7th ed.
Paris: E. Bernard & Cie. 1889
Page 610.

Plot of Jauge de Paris 1857




Figure 2: Jauge de Paris 1857 FWS.inc

A more recent version of this guage:

1.6.3 Correspondence Between Paris Gauge and Wire Diameter

Updated on: 9:32 AM 2/10/2026

Source: TECHNISSAGE — 69400 VILLEFRANCHE SUR SAONE, France

The Paris Gauge (JDP) is an old measuring tool that allowed the diameter of wires to be found.

Used in the Middle Ages it was used by iron merchants and all craftsmen using thread.

Even today, wire diameter is sometimes expressed in Paris gauge.

Gague Vs. Diameter			
JDP	mm	JDP	mm
1	0,60	12	1,80
2	0,70	13	2,00
3	0,80	14	2,20
4	0,90	15	2,40
5	1,00	16	2,70
6	1,10	17	3,00
7	1,20	18	3,40
8	1,30	19	3,90
9	1,40	20	4,40
10	1,50	21	4,90
11	1,60	22	5,40

1.6.4 Jauge Japy

Gauge	Diameter in Millimeters	Gauge	Diameter in Millimeters
10	1.45	28	9.4
11	1.60	29	10.0
12	1.75	30	10.5
13	1.90	31	11.0
14	2.05	32	11.5
15	2.2	33	12.5
16	2.4	34	13.5
17	2.7	35	14.5
18	3.0	36	15.5
19	3.5	37	16.5
20	4.0	38	17.5
21	4.6	39	18.5
22	5.2	40	19.5
23	5.9	41	20.5
24	6.6	42	21.5
25	7.3	43	22.5
26	8.0	44	23.5
27	8.7		

Table 9: Jauge Japy

Source

Hardware Tables, Formulae and Recipes... 6th edition.
 London: The Ironmonger, 1924. Pages 3 and 63, which differ.

Plot of Jauge Japy




Figure 3: Jauge Japy FWS.inc

1.6.5 Jauge de Limoges

Gauge	Diameter in Millimeters	Gauge	Diameter in Millimeters
0	0.39	13	1.91
1	0.45	14	2.02
2	0.56	15	2.14
3	0.67	16	2.25
4	0.79	17	2.84
5	0.90	18	3.40
6	1.01	19	3.95
7	1.12	20	4.50
8	1.24	21	5.10
9	1.35	22	5.65
10	1.46	23	6.20
11	1.68	24	6.80
12	1.80		

Table 10: Jauge de Limoges

Source

Cl. de Laharpe.
Notes & Formules de L'Ingénieur et du Constructeur-Mécanicien.
7th ed.
Paris: E. Bernard & Cie. 1889
Page 610.

Plot of Jauge de Limoges




Figure 4: Jauge de Limoges FWS.inc

1.6.6 Jauge Carcasse or du Commerce

Gauge	Diameter in Millimeters	Gauge	Diameter in Millimeters
P	0.50	32	0.17
12	0.47	34	0.14
14	0.44	36	0.12
16	0.40	38	0.11
18	0.37	40	0.10
20	0.34	42	0.09
22	0.32	44	0.08
24	0.29	46	0.07
26	0.26	48	0.06
28	0.22	50	0.05
30	0.20		

Table 11: Jauge de Limoges

Source

Cl. de Laharpe.
Notes & Formules de L'Ingénieur et du Constructeur-Mécanicien.
7th ed.
Paris: E. Bernard & Cie. 1889
Page 610.

Plot of Jauge carcasse or du Commerce




Figure 5: Jauge carcasse or du Commerce FWS.inc

1.6.7 Sources for French wire gauges

There is no doubt but that English wire gauges have been largely used on the continent of Europe in former times, and especially the so-called Birmingham wire-gauge. At present this wire gauge is still used in Belgium, Russia, Sweden, Norway, and Denmark. The new standard gauge is only being introduced by degrees. In Germany, the Birmingham wire gauge was used up to the year 1878, although the ancient Westphalian wire gauge and also the French gauge (or *jauge de Paris*) were used besides, to a small extent. In 1872, the German wire drawers adopted the so-called millimetre wire gauge, which is at present used throughout Germany and Austria, other wire gauges only being used occasionally. The millimetre gauge indicates the size of wire by tenths of a millimetre, so that for instance the No. 42 wire would be 4.2 mm. thick, and No. 4 wire would be 0.4 mm. thick. Certain standard sizes are, however, adopted by preference, coming up very nearly to the old Birmingham wire gauge, say:

As regards the system of measurement employed in Germany, wire gauges, i.e., plates of steel with notches representing the various sizes of wire, are still much used in the works, but in addition the micrometer or screw gauge is much employed, allowing the measurement of the size of wire to the smallest fraction of a millimetre.

In France, Spain, Italy, Switzerland, Greece, and Asia Minor, the French gauge, and principally the so-called *jauge de Paris* of 1857, is used. This gauge indicates the size of wire by numbers having certain equivalents in millimetres; and, contrary to the Birmingham wire gauge, where the smallest number indicates the largest size, in the French gauge the smallest number indicates the smallest size.

The *jauge "japy"*, similar to the *jauge de Paris*, but with slightly smaller sizes for the different numbers, is also used to some extent in France and Switzerland; for the finer wires, card wire, copper wire, etc., the so-called *jauge "carcasse"* is in use.

With regard to Great Britain and the British colonies, they all now use the new standard wire gauge. In the United States of America, hitherto the Stubbs' Birmingham wire gauge has, we believe, been mostly used, besides Washburn & Moen's, and Brown and Sharpe's wire gauges.

If we are not mistaken there is a tendency in the United States to the adoption of the millimetre gauge. If this gauge should really be adopted in the states, the Americans will show that they are readier to take up an improvement than their English cousins, the millimetre gauge having been frequently proposed in England, but always declined on account of the conservative opposition it encountered. In South America both the Birmingham wire gauge or the new standard gauge and the *jauge de Paris* are used according to whether buyers have been accustomed to purchase in England or in France, the French imports of wire having of late been replaced by imports from Germany.

We are used to sell in the export market to whatever gauge may be desired.

In concluding, we beg to give you our opinion that the best system of measuring is the millimetre gauge, and that this gauge will be used to greater extent in the future; this will, however, greatly depend upon whether England will do away with her ancient system of measures, weights and money, and replace it by the far simpler metric system. This, we believe, is only a question of time.

A letter from Felten & Guillaume, of Müllheim, near Cologne, "the largest makers in the world of iron and steel telegraph wire" replying to an inquiry from a M. Welles, who submitted it to *The Electrical World*. It subsequently appeared in *The Electrician and Electrical Engineer*, vol. 5, page 476 (Dec. 1885). Welles commented that "the statements made as to usage in different countries refer to line wire, and not to sheet metal, fine copper wires, etc."

1.7 Metric Wire Sizes

1.7.1 Metrically-sized equivalents for SWG-sized electrical cables

Source: Sizes.com's web site.

The British Standard Wire Gauge (not to be confused with the Steel Wire Gauge, also with the symbol SWG) is based on the wire's diameter. The metric conductor sizes are based on the nominal area of the cross section of the conductor. The actual cross-sectional areas depend in part upon the stranding of the cable.

A cable with the metric value shown will have at least as much carrying capacity as the SWG cable for which it is being substituted. In other words, values have always been rounded up. For that reason,

Warning: do not use this table to find the SWG equivalent to a metric cable.

The table assumes the metric-sized cable is substituted for an SWG-sized cable **Warning: of the same type.** It cannot be used, for example, to find a metrically-sized aluminum cable to substitute for a copper SWG cable. If the types are dissimilar, consult the cable manufacturer's literature to determine capacity.

For Standard Wire Gauge	Substitute Metric Nominal Cross-sectional Area square millimeters
7/0	150
6/0	120
5/0	95
4/0	95
3/0	95
2/0	70
0	70
1	50
2	50
3	35
4	35
5	25
6	25
7	16
8	16
9	16
10	10
11	10
12	6
13	6
14	4
15	4
16	2.5
17	2.5
18	1.5
19	1
20	0.75
21	0.75
22	0.5

Table 12: Metrically-sized equivalents for SWG

1.7.2 Metric-sized equivalents for AWG-sized electrical cables

Source: [Sizes.com](https://www.sizes.com)'s web site.

The American Wire Gauge is based on the wire's diameter; the metric conductor sizes are based on the nominal area of the cross section of the conductor. The actual cross-sectional areas depend in part upon the stranding of the cable.

A cable with the metric value shown will have at least as much carrying capacity as the AWG cable for which it is being substituted. In other words, values have always been rounded up. For that reason, **Warning: do not use this table to find the AWG equivalent to a metric cable.**

The table assumes the metric-sized cable will be substituted for an AWG-sized cable **Warning: of the same type.** It cannot be used, for example, to find a metric-sized aluminum cable to substitute for a copper AWG cable. If the types are dissimilar, consult the cable manufacturer's literature to determine capacity.

American Wire Gauge (AWG)	Substitute this Metric Nominal Cross-sectional Area, square millimeters
6/0	185
5/0	150
4/0	120
3/0	95
2/0	70
0	70
1	50
2	35
3	35
4	25
5	25
6	16
7	16
8	10
9	10
10	6
11	6
12	4
13	4
14	2.5
15	2.5
16	1.5
17	1.5
18	1
19	0.75
20	0.75
21	0.5

Table 13: Metric-sized equivalents for AWG

1.8 Making Wire

Source: [Sizes.com](https://www.sizes.com)'s web site.

In 1910 Hugh Tiemann wrote the following concise description of the manufacture of steel wire. The **boldface emphases** are his.

Wire.— This is the name given to small metal filaments (usually round) produced in pieces of considerable length by **drawing**, *i.e.*, successively reducing (and thereby extending) the section by repeatedly pulling it cold (**cold drawing**) through tapered holes in a die or **draw plate (block, die plate)**. Drawing is necessary as it is impracticable to roll such small sections commercially.

Billets are first reduced, in a rolling mill, to **wire rods** (rounds) about 0.2" to 0.3" in diameter, which are coiled up into **bundles**. These bundles are placed in a **pickling bath** of dilute sulphuric acid, heated by steam, to remove the scale, and are then transferred to the **rinsing bath** to remove the greater part of the acid, after which they are put on a revolving frame and sprayed with water to still further remove the acid; this causes a certain amount of rust to form on the surface, which acts later as a slight lubricant and is known as a **rust coating** or **water coating**. The last traces of acid are eliminated by treatment in the **lime bath (liming)**, after which the bundles are dried (**baked**) at a low temperature in a furnace called the **baker**. If the wire is to be **bright finished** (*i.e.*, unannealed), it is transferred from the rinsing bath immediately to the lime bath.

The **draw plate** is a piece of hard (high carbon) steel (more rarely cast iron) containing a number of **holes** through which the wire is drawn. Usually all those in one plate are of the same size and the wire is passed through successive plates, each hole serving for one (sometimes two) bundles. After use the plates are annealed (as the metal around the holes has been hardened), the holes reduced by hammering and then opened up to the exact size by punching (**pricking**). The plates used for the first few reductions are sometimes referred to as the **roughing blocks**, **nipping blocks**, or **nippers**; those for the last, as **finishing blocks**.

Drawing is performed on the **draw bench**, which comprises the draw plate and a power reel for pulling the wire through. To start the wire through the hole, it must be pointed either with a small hammer, or by a pair of small rollers with grooves of different sizes, given a rocking movement (like an alligator shears) by an eccentric. The wire is then pulled through by a pair of tongs (**grippers** or **nippers**) attached to a crank shaft, giving a reciprocating (back and forth) movement, until there is a sufficient length to attach it to the power reel. The term **ratch** is used for the pull of the wire through the die at one operation where a straight pull and not a reel is used. The plate is sometimes tilted backward at a slight angle to **kill** the wire, *i.e.*, prevent the tendency to spring out into an unmanageably large coil on removal from the reel. To reduce the friction in drawing, the wire must be coated with some substance which acts as a lubricant. In **dry drawing**, grease is employed: it is piled against the back of the draw plate around the hole, and one application serves for a number of reductions. In **wet drawing**, the wire is given a **lees coating** by passing it through **lees liquor** composed of water and some kind of flour, sometimes fermented and sometimes mixed with milk of lime. A **copper coating (lacquer)** is obtained by treating the wire with a weak acidulated solution of copper sulphate, and then usually passing it through lees liquor before drawing. After this treatment it is known as **lacquered**, **straw-tinted**, or **coppered wire**; this method is sometimes called the **liquor-bright process**. If the finished wire is to be coppered, it must receive an additional treatment.

Multiple drawing is where the wire is drawn through a number of dies simultaneously, being reeled up only after passing through the last, instead of after each plate. In this case, to avoid breaking, it is necessary to provide a power reel between each pair of holes, around which the wire is given a couple of turns. Passing the wire through the various dies and around the reels is called **stringing up**. After about 8 to 10 **holes** (hole in this sense means pass or reduction) the wire is so much hardened that it must be reannealed, etc.,

⁰Making Wire.inc 13 February 2026 14:52

before drawing can be continued. This fine wire is sometimes **batted**, *i.e.*, beaten with wooden sticks while being washed after pickling.

Plain drawn wire (**bench hardened wire**) is wire in the condition in which it leaves the last hole, without any further treatment.; **Plain annealed wire** is where it is annealed in closed iron pots to render it soft and pliable. **Galvanized wire** is annealed and then coated with zinc (spelter). In galvanizing, the wire is passed (a) through a lead bath to anneal it; (b) through a weak pickling solution to remove the scale formed; (c) through a rinsing bath; and (d) through the molten spelter contained in the **galvanizing pan**. The excess of zinc is removed by drawing it through plugs of asbestos, called **wipers**. The wire is kept below the surface of the zinc by passing it under heavy toothed bars called **sinkers**. In modern practice a number of wires or strands are treated simultaneously, the whole series of operations being continuous, and one power reel serving to pull each strand through (**Bedson's continuous galvanizing process**). Attempts have been made to produce **bright annealed wire** by annealing in a reducing atmosphere so no oxide or scale will be formed. **Tinman's wire** is a soft bright-drawn wire used in the manufacture of various tin plate goods. **Improved steel wire** or **patented steel wire**, after finishing in the usual manner, is heated in a muffle, quenched in oil, and tempered in molten lead. **Plow steel wire** is made from a fine grade of high-carbon, crucible steel, and is so called because it was originally used for dragging steam plows. **Gun screw wire** is a name sometimes employed for wire made from a high grade of refined wrought iron. **B. B. wire**, **E. B. B. wire**, or **four-sided charcoal wire** were grades in England, used for telegraphic work, made of fagots composed of puddled billets in the center, and four flats outside, of (a) best, best puddled iron (b) or top and bottom of charcoal iron with sides of best, best puddled iron, or (c) charcoal iron all around, respectively. Instead of cleaning wire with acid, it is sometimes put into a **scouring barrel**, in which it is rotated with some cleaning material.

Hugh P. Tiemann
Iron and Steel. A Pocket Encyclopedia
New York: McGraw-Hill Book Company, 1910

A A table comparing diameters of some common gauges

Source: [Sizes.com](https://www.sizes.com/)'s web site.

Note that 4/0 (pronounced "four aught") is an abbreviation for 0000, 2/0 for 00, and so on.

Common Wire Gauges, Based on Diameter in Inches							
Gauge	American or Brown & Sharpe Wire Gauge	Birming- ham or Stubs' Iron Wire	Stubs' Steel Wire Gauge	Washburn & Moen, Roebbling or American Steel and Wire Co.	Imper- ial Wire Gauge	Whit- worth's	Steel Wire Gauge, Waterbury Co., 1917
9/0	—	—	—	—	—	—	0.005
8/0	—	—	—	—	—	—	0.0055
7/0	—	—	—	0.4900	0.5000	—	0.006
6/0	0.5800	—	—	0.4615	0.4640	—	0.0065
5/0	0.5165	0.500	—	0.4305	0.4320	—	0.007
4/0	0.4600	0.454	—	0.3938	0.4000	—	0.0075
3/0	0.4096	0.425	—	0.3625	0.3720	—	0.008
2/0	0.3648	0.380	—	0.3310	0.3480	—	0.0085
0	0.3249	0.340	—	0.3065	0.3240	—	0.009
1	0.2893	0.300	0.227	0.2830	0.3000	0.001	0.010
2	0.2576	0.284	0.219	0.2625	0.2760	0.002	0.011
3	0.2294	0.259	0.212	0.2437	0.2520	0.003	0.012
4	0.2043	0.238	0.207	0.2253	0.2320	0.004	0.013
5	0.1819	0.220	0.204	0.2070	0.2120	0.005	0.014
6	0.1620	0.203	0.201	0.1920	0.1920	0.006	0.016
7	0.1443	0.180	0.199	0.1770	0.1760	0.007	0.018
8	0.1285	0.165	0.197	0.1620	0.1600	0.008	0.020
9	0.1144	0.148	0.194	0.1483	0.1440	0.009	0.022
10	0.1019	0.134	0.191	0.1350	0.1280	0.010	0.024
11	0.0907	0.120	0.188	0.1205	0.1160	0.011	0.026
12	0.0808	0.109	0.185	0.1055	0.1040	0.012	0.028
13	0.0720	0.095	0.182	0.0915	0.0920	0.013	0.030
14	0.0641	0.083	0.180	0.0800	0.0800	0.014	0.032
15	0.0571	0.072	0.178	0.0720	0.0720	0.015	0.034
16	0.0508	0.065	0.175	0.0625	0.0640	0.016	0.036
17	0.0453	0.058	0.172	0.0540	0.0560	0.017	0.038
18	0.0403	0.049	0.168	0.0475	0.0480	0.018	0.040

Continued on the next page.

Common Wire Gauges, Based on Diameter in Inches							
Gauge	American or Brown & Sharpe Wire Gauge	Birming- ham or Stubs' Iron Wire	Stubs' Steel Wire Gauge	Washburn & Moen, Roebling or American Steel and Wire Co.	Imper- ial Wire Gauge	Whit- worth's	Steel Wire Gauge, Waterbury Co., 1917
19	0.0359	0.042	0.164	0.0410	0.0400	0.019	0.042
20	0.0320	0.035	0.161	0.0348	0.0360	0.020	0.044
21	0.0285	0.032	0.157	0.03175	0.0320	0.021	0.046
22	0.0253	0.028	0.155	0.0286	0.0280	0.022	0.048
23	0.0226	0.025	0.153	0.0258	0.0240	0.023	0.051
24	0.0201	0.022	0.151	0.0230	0.0220	0.024	0.055
25	0.0179	0.020	0.148	0.0204	0.0200	0.025	0.059
26	0.0159	0.018	0.146	0.0181	0.0180	0.026	0.063
27	0.0142	0.016	0.143	0.0173	0.0164	0.027	0.067
28	0.0126	0.014	0.139	0.0162	0.0149	0.028	0.071
29	0.0113	0.013	0.134	0.0150	0.0136	0.029	0.074
30	0.0100	0.012	0.127	0.0140	0.0124	0.030	0.078
31	0.0089	0.010	0.120	0.0132	0.0116	0.031	0.082
32	0.0080	0.009	0.115	0.0128	0.0108	0.032	0.086
33	0.0071	0.008	0.112	0.0118	0.0100	0.033	0.090
34	0.0063	0.007	0.110	0.0104	0.0092	0.034	0.094
35	0.0056	0.005	0.108	0.0095	0.0084	0.035	0.098
36	0.0050	0.004	0.106	0.0090	0.0076	0.036	0.102
37	0.0045	—	0.103	—	0.0068	0.037	0.106
38	0.0040	—	0.101	—	0.0060	0.038	0.112
39	0.0035	—	0.099	—	0.0052	0.039	0.118
40	0.0031	—	0.097	—	0.0048	0.040	0.125
41	0.0028	—	0.095	—	0.0044	0.041	0.132
42	0.0025	—	0.092	—	0.0040	0.042	0.139
43	0.0022	—	0.088	—	0.0036	0.043	0.146
44	0.00198	—	0.085	—	0.0032	0.044	0.153
45	0.00176	—	0.081	—	0.0028	0.045	0.160
46	0.00157	—	0.079	—	0.0024	0.046	—
47	0.00140	—	0.077	—	0.0020	0.047	—
48	0.00124	—	0.075	—	0.0016	0.048	—

Common Wire Gauges, Based on Diameter in Inches							
Gauge	American or Brown & Sharpe Wire Gauge	Birming- ham or Stubs' Iron Wire	Stubs' Steel Wire Gauge	Washburn & Moen, Roebling or American Steel and Wire Co.	Imper- ial Wire Gauge	Whit- worth's	Steel Wire Gauge, Waterbury Co., 1917
49	0.001108	—	0.072	—	0.0012	0.049	—
50	0.00099	—	0.069	—	0.0010	0.050	—
51	—	—	0.066	—	—	0.051	—
52	—	—	0.063	—	—	0.052	—
53	—	—	0.058	—	—	0.053	—
54	—	—	0.055	—	—	0.054	—
55	—	—	0.050	—	—	0.055	—
56	—	—	0.045	—	—	0.056	—
57	—	—	0.042	—	—	0.057	—
58	—	—	0.041	—	—	0.058	—
59	—	—	0.040	—	—	0.059	—
60	—	—	0.039	—	—	0.060	—
61	—	—	0.038	—	—	0.061	—
62	—	—	0.037	—	—	0.062	—
63	—	—	0.036	—	—	0.063	—
64	—	—	0.035	—	—	0.064	—
65	—	—	0.033	—	—	0.065	—
66	—	—	0.032	—	—	0.066	—
67	—	—	0.031	—	—	0.067	—
68	—	—	0.030	—	—	0.068	—
69	—	—	0.029	—	—	0.069	—
70	—	—	0.027	—	—	0.070	—
71	—	—	0.026	—	—	0.071	—
72	—	—	0.024	—	—	0.072	—
73	—	—	0.023	—	—	0.073	—
74	—	—	0.022	—	—	0.074	—
75	—	—	0.020	—	—	0.075	—
76	—	—	0.018	—	—	0.076	—
77	—	—	0.016	—	—	0.077	—
78	—	—	0.015	—	—	0.078	—

<i>Continued from the previous page.</i>							
Common Wire Gauges, Based on Diameter in Inches							
Gauge	American or Brown & Sharpe Wire Gauge	Birming- ham or Stubs' Iron Wire	Stubs' Steel Wire Gauge	Washburn & Moen, Roebling or American Steel and Wire Co.	Imper- ial Wire Gauge	Whit- worth's	Steel Wire Gauge, Waterbury Co., 1917
79	—	—	0.014	—	—	0.079	—
80	—	—	0.013	—	—	0.080	—


Table 14: Comparing Diameters of some Common Gauges

A.1 American or Brown & Sharpe Wire Gauge

Gauge	Size	Gauge	Size
000 000	0.5800	23	0.0226
00 000	0.5165	24	0.0201
0 000	0.4600	25	0.0179
000	0.4096	26	0.0159
00	0.3648	27	0.0142
0	0.3249	28	0.0126
1	0.2893	29	0.0113
2	0.2576	30	0.0100
3	0.2294	31	0.0089
4	0.2043	32	0.0080
5	0.1819	33	0.0071
6	0.1620	34	0.0063
7	0.1443	35	0.0056
8	0.1285	36	0.0050
9	0.1144	37	0.0045
10	0.1019	38	0.0040
11	0.0907	39	0.0035
12	0.0808	40	0.0031
13	0.0720	41	0.0028
14	0.0641	42	0.0025
15	0.0571	43	0.0022
16	0.0508	44	0.00198
17	0.0453	45	0.00176
18	0.0403	46	0.00157
19	0.0359	47	0.00140
20	0.0320	48	0.00124
21	0.0285	49	0.001108
22	0.0253	50	0.00099

Table 15: American or Brown & Sharpe Wire Gauge

Plot of American or Brown & Sharpe Wire Gauge



Sat Jan 24 13:11:35 2026


Figure 6: American or Brown & Sharpe Wire Gauge `Common Gauges.inc`

A.2 Birmingham or Stubs' Iron Wire

Gauge	Size	Gauge	Size
00 000	0.500	17	0.058
0 000	0.454	18	0.049
000	0.425	19	0.042
00	0.380	20	0.035
0	0.340	21	0.032
1	0.300	22	0.028
2	0.284	23	0.025
3	0.259	24	0.022
4	0.238	25	0.020
5	0.220	26	0.018
6	0.203	27	0.016
7	0.180	28	0.014
8	0.165	29	0.013
9	0.148	30	0.012
10	0.134	31	0.010
11	0.120	32	0.009
12	0.109	33	0.008
13	0.095	34	0.007
14	0.083	35	0.005
15	0.072	36	0.004
16	0.065		

Table 16: Birmingham or Stubs' Iron Wire Gauge

Plot of Birmingham or Stubs' Iron Wire Gauge



Sat Jan 24 13:11:36 2026


Figure 7: Birmingham or Stubs' Iron Wire Gauge `Common Gauges.inc`

A.3 Stubs' Steel Wire Gauge

Gauge	Size	Gauge	Size	Gauge	Size	Gauge	Size
1	0.227	21	0.157	41	0.095	61	0.038
2	0.219	22	0.155	42	0.092	62	0.037
3	0.212	23	0.153	43	0.088	63	0.036
4	0.207	24	0.151	44	0.085	64	0.035
5	0.204	25	0.148	45	0.081	65	0.033
6	0.201	26	0.146	46	0.079	66	0.032
7	0.199	27	0.143	47	0.077	67	0.031
8	0.197	28	0.139	48	0.075	68	0.030
9	0.194	29	0.134	49	0.072	69	0.029
10	0.191	30	0.127	50	0.069	70	0.027
11	0.188	31	0.120	51	0.066	71	0.026
12	0.185	32	0.115	52	0.063	72	0.024
13	0.182	33	0.112	53	0.058	73	0.023
14	0.180	34	0.110	54	0.055	74	0.022
15	0.178	35	0.108	55	0.050	75	0.020
16	0.175	36	0.106	56	0.045	76	0.018
17	0.172	37	0.103	57	0.042	77	0.016
18	0.168	38	0.101	58	0.041	78	0.015
19	0.164	39	0.099	59	0.040	79	0.014
20	0.161	40	0.097	60	0.039	80	0.013

Table 17: Stubs' Steel Wire Gauge

Plot of Stubs' Steel Wire Gauge



Sat Jan 24 13:11:39 2026


Figure 8: Stubs' Steel Wire Gauge `Common Gauges.inc`

A.4 Washburn & Moen, Roebling or American Steel and Wire Co.

Gauge	Size	Gauge	Size
0 000 000	0.4900	16	0.0625
000 000	0.4615	17	0.0540
00 000	0.4305	18	0.0475
0 000	0.3938	19	0.0410
000	0.3625	20	0.0348
00	0.3310	21	0.03175
0	0.3065	22	0.0286
1	0.2830	23	0.0258
2	0.2625	24	0.0230
3	0.2437	25	0.0204
4	0.2253	26	0.0181
5	0.2070	27	0.0173
6	0.1920	28	0.0162
7	0.1770	29	0.0150
8	0.1620	30	0.0140
9	0.1483	31	0.0132
10	0.1350	32	0.0128
11	0.1205	33	0.0118
12	0.1055	34	0.0104
13	0.0915	35	0.0095
14	0.0800	36	0.0090
15	0.0720		

Table 18: Washburn & Moen, Roebling or American Steel and Wire Co. Gauge

Plot of Washburn & Moen, Roebling or American Steel and Wire Co. Gauge



Sun Jan 25 17:22:30 2026


Figure 9: Washburn & Moen, Roebling or American Steel and Wire Co. Gauge `Common Gauges.inc`

A.5 Imperial Wire Gauge

Gauge	Size	Gauge	Size
0 000 000	0.5000	23	0.0240
000 000	0.4640	24	0.0220
00 000	0.4320	25	0.0200
0 000	0.4000	26	0.0180
000	0.3720	27	0.0164
00	0.3480	28	0.0149
0	0.3240	29	0.0136
1	0.3000	30	0.0124
2	0.2760	31	0.0116
3	0.2520	32	0.0108
4	0.2320	33	0.0100
5	0.2120	34	0.0092
6	0.1920	35	0.0084
7	0.1760	36	0.0076
8	0.1600	37	0.0068
9	0.1440	38	0.0060
10	0.1280	39	0.0052
11	0.1160	40	0.0048
12	0.1040	41	0.0044
13	0.0920	42	0.0040
14	0.0800	43	0.0036
15	0.0720	44	0.0032
16	0.0640	45	0.0028
17	0.0560	46	0.0024
18	0.0480	47	0.0020
19	0.0400	48	0.0016
20	0.0360	49	0.0012
21	0.0320	50	0.0010
22	0.0280		

Table 19: Imperial Wire Gauge

Plot of Imperial Wire Gauge



Sat Jan 24 13:11:38 2026


Figure 10: Imperial Wire Gauge Common Gauges.inc

A.6 Whitworth's

Gauge	Size	Gauge	Size	Gauge	Size	Gauge	Size
1	0.001	21	0.021	41	0.041	61	0.061
2	0.002	22	0.022	42	0.042	62	0.062
3	0.003	23	0.023	43	0.043	63	0.063
4	0.004	24	0.024	44	0.044	64	0.064
5	0.005	25	0.025	45	0.045	65	0.065
6	0.006	26	0.026	46	0.046	66	0.066
7	0.007	27	0.027	47	0.047	67	0.067
8	0.008	28	0.028	48	0.048	68	0.068
9	0.009	29	0.029	49	0.049	69	0.069
10	0.010	30	0.030	50	0.050	70	0.070
11	0.011	31	0.031	51	0.051	71	0.071
12	0.012	32	0.032	52	0.052	72	0.072
13	0.013	33	0.033	53	0.053	73	0.073
14	0.014	34	0.034	54	0.054	74	0.074
15	0.015	35	0.035	55	0.055	75	0.075
16	0.016	36	0.036	56	0.056	76	0.076
17	0.017	37	0.037	57	0.057	77	0.077
18	0.018	38	0.038	58	0.058	78	0.078
19	0.019	39	0.039	59	0.059	79	0.079
20	0.020	40	0.040	60	0.060	80	0.080

Table 20: Whitworth's Gauge

Plot of Whitworth's Gauge



Sun Jan 25 17:22:36 2026

Figure 11: Whitworth's Gauge `Common Gauges.inc`

A.7 Steel Wire Gauge, Waterbury Co., 1917

Gauge	Size	Gauge	Size
000 000 000	0.005	19	0.042
00 000 000	0.0055	20	0.044
0 000 000	0.006	21	0.046
000 000	0.0065	22	0.048
00 000	0.007	23	0.051
0 000	0.0075	24	0.055
000	0.008	25	0.059
00	0.0085	26	0.063
0	0.009	27	0.067
1	0.010	28	0.071
2	0.011	29	0.074
3	0.012	30	0.078
4	0.013	31	0.082
5	0.014	32	0.086
6	0.016	33	0.090
7	0.018	34	0.094
8	0.020	35	0.098
9	0.022	36	0.102
10	0.024	37	0.106
11	0.026	38	0.112
12	0.028	39	0.118
13	0.030	40	0.125
14	0.032	41	0.132
15	0.034	42	0.139
16	0.036	43	0.146
17	0.038	44	0.153
18	0.040	45	0.160

Table 21: Steel Wire Gauge, Waterbury Co., 1917

Plot of Steel Wire Gauge, Waterbury Co., 1917 Gauge




Figure 12: Steel Wire Gauge, Waterbury Co., 1917 Gauge `Common Gauges.inc`

A.8 Sizes of Numbers of the United States Standard Gauge

Updated on: 12:23 PM 2/10/2026

Source: Brown & Sharpe Catalog No. 29, 1924, pages 172 and 173. For gauges 39 through 44 the source was Lufkin Precision Tools, Catalog No. 7, page T138.

This is an slightly changed item from the Brown & Sharpe catalog about an act of Contress that established this set of values as the "Standard Gauge Sizs" for use in the United States.

Yes the title of this section came directly form the page in the Brown & Sharpe catalog. It is not a typing error from me.

For Sheet and Plate Iron and Steel

An Act

Establishing a Standard Gauge for Sheet and Plate Iron and Steel.


Be it enacted by the Senate and the House of Representatives of the Uniteed States of Americal in Congress assembled:

That for the purpose of securing uniformity the following is established as the only gauge for sheet and plate iron and steel in the United States of America nameley:

Gauge	Thickness in Frac- tions	Thickness in Deci- mal	Gauge	Thickness in Frac- tions	Thickness in Deci- mal	Gauge	Thickness in Frac- tions	Thickness in Deci- mal
0 000 000	1/2	.5	11	1/8	.125	28	1/64	.015625
000 000	15/32	.46875	12	7/64	.109375	29	9/640	.0140625
00 000	7/17	.4375	13	3/32	.09375	30	1/80	.0125
0 000	13/32	.40625	14	5/64	.078125	31	7/640	.0109375
000	3/8	.375	15	9/128	.0703125	32	13/1280	.01015625
00	11/32	.34375	16	1/16	.0625	33	3/320	.009375
0	5/16	.3125	17	9/160	.05625	34	11/1280	.00859375
1	9/32	.28125	18	1/20	.05	35	5/640	.0078125
2	17/64	.265625	19	7/160	.04375	36	9/1280	.00703125
3	1/4	.25	20	3/80	.0375	37	17/2560	.006640625
4	15/64	.235375	21	11/320	.034375	38	1/160	.00625
5	7/32	.21875	22	1/32	.03125	39	15/2560	.005859375
6	13/64	.203125	23	9/320	.028125	40	7/1280	.00546875
7	3/16	.1875	24	1/40	.025	41	27/5120	.0052734375
8	11/64	.171875	25	7/320	.021875	42	13/2560	.005078125
9	5/32	.15625	26	3/160	.01875	43	25/5120	.0048828125
10	9/64	.140625	27	11/640	.0171875	44	3/640	.0046875

Table 22: United States Standard Gage

⁰BandSamericanstandard.inc 13 February 2026 14:52



Sat Jan 17 12:37:55 2026

Figure 13: American Standard Gauge for Sheet and Plate Iron and Steel `BandSamericanstandard.inc`

B Privacy Statement from Sizes.com

Source: [Sizes.com](https://www.sizes.com/privacy)

Effective 14 July 2023

For GDPR and CCPA purposes: we have fewer than 250 employees (far fewer) and gross annual revenue of less than US\$25,000,000 (many orders of magnitude less). We ourselves do not buy, sell, or share information on our readers, or collect it, except as detailed below.

This website, **Sizes.com**, provides information on a variety of topics. Some pages include links to other websites, but this Privacy Policy applies only to **Sizes.com** and not to any other website. If you follow a link in **Sizes.com** to another website, that site's privacy policy, if any, applies, and we are in no way responsible for that external site's practices.

We do not sell anything. We have no user accounts. We do not ask readers to register.

We do NOT collect any personally-identifiable information from users browsing this site. Since we do not store any information about you, we cannot rent, sell or share it with other parties, or even you. It doesn't exist.

In the information below, we use the phrase "anonymous data." This means data that does not include information sufficient to identify a particular individual, such as name and address. You should be aware that researchers have shown that by using large databases even "anonymous data" can be traced back to a particular individual. Everyone is unique, so there is probably only one person who lives in Idaho, subscribes to *Popular Mechanics*, sings in the local barbershop quarter, and raises alpaca, even though all that information had been furnished without a name attached.

Terms entered in the site search box

We save in a log the words users enter into the "search this site" form. We do this so that we can know what topics people want to find on the site. We use that information in planning new pages. However, we save only the words entered. We do not save anything about who entered the words, where they came from, or what they did next. We have no record connecting a word typed into the search box with the identity of the person who typed it.

The site search engine is a simple one that runs on our host's server. It is not an external third-party service like Google, Bing, Baidu, Yahoo! or Yandex, or even DuckDuckGo.

Information you enter into a form

Any information you enter into a form on a page in **Sizes.com** (for example, in one of the calculators), other than the site search form, is processed on your own computer. It is not sent back to us. (For the technically well-informed: no GET or POST actions.) For example, suppose you enter your height and weight in the body mass index calculator. Your height and weight will not be sent to us; they will be used by your own computer to calculate your body mass index. The result, your body mass index, will not be sent to us either. Further, the information will not be stored in a cookie, so if you leave the page and come back, you will have to re-enter it.

Email

If you email us using the link at the bottom of a page, that email will contain whatever name and return address you provide in the "from" line, and other data in the header. We save these emails because they often contain valuable comments or suggestions that help us revise and improve **Sizes.com** pages.

We do not merge any personally-identifiable information from emails you send us with other anonymous data collected on our website.

⁰Privacy.inc 13 February 2026 14:52

Google Analytics

We use the Google Analytics service (GA). When you open a page on this website, the analytics program sets cookies on your machine. See a description of the service by Google at: policies.google.com/technologies/types.

The value of the analytics service to us is that it tells us which pages are most often visited, in what countries the site is most used, and so on. We use this information in guessing what you would like us to do next.

Through GA we receive records of anonymous data such as traffic logs, numbers of visits or clicks on a given page, pages viewed or links to our website. We do this to improve the site's navigability. We use IP addresses for gathering website statistics. We also store IP addresses on our server because if our site becomes corrupted such information is helpful in discovering the cause of the corruption. The recording of IP addresses, at least temporarily, is essential to the operation of the web.

We aggregate this anonymous data as part of managing, maintaining and reporting on use of our website. We may share this anonymous data with third parties for the limited purpose of reporting on use of our website, or to comply with applicable law. We do not rent, sell or share any anonymous data collected on this website with third parties for marketing purposes.

Google makes available a tool you can use to disable GA, the Google Analytics Opt-out Browser Add-on tools.google.com/dlpage/gaoptout/. This browser add-on will work with the version of GA we have used (on-page javascript). Google is switching (1 July 2023) to a new analytics system, GA4, and at this point we are not certain what the result will be.

We have not enabled the Google Analytics Advertising Features. See support.google.com/analytics/answer/6004245.

Advertisements

Advertisements appearing on this web site have been placed through the Google AdSense program. We have opted out of the AdSense feature which enables it to show ads based on user interest categories, and visitation; information from this site is not used by Google to help create interest categories. Beyond that, we have little control over the ads. It is possible for ads to set cookies and trackers.

Some advertisers may have cookies on your machine from your previous visits to other sites, and may use information (NOT including your name, address, email address or telephone number) about your visits to this and other websites in order to provide advertisements about goods and services of interest to you. If you would like more information about this practice and to know your choices about not having this information used by these companies, visit policies.google.com/technologies/ads.html.

If you are concerned about privacy issues raised by some ads, you can employ an ad-blocker on your browser. Two that we can recommend are [adblockplus.org/AdBlockPlus](https://adblockplus.org/) and www.ghostery.com/. Of course, by doing so you may be cutting off the cash flow to some of your favorite sites. AdBlockPlus has an "Acceptable Ads" option which allows through non-obnoxious, non-tracking ads.

Changes in the Privacy Policy

As the web and this website evolves, this Privacy Policy may be revised from time to time to accommodate changes in the Internet, the legal environment, and this website. We reserve the right to amend this Privacy Policy at any time, for any reason. Notice of such amendments will be posted as an updated Privacy Policy on this website, and an effective date will be shown. Users are encouraged to occasionally revisit Sizes.com's Privacy Policy.

Ownership

Sizes, Inc. (a Delaware corporation) is the sole owner of all information collected on this site. None of its stock is held by any other corporate entity.

Copyright © 2000-2023 Sizes, Inc. All rights reserved.
Last revised: 14 August 2023.

C Conditions of Use, from Sizes.com

Source: [Sizes.com](https://www.sizes.com)

Conditions of Use

The Sizes Web site (the "Site") is a service provided by Sizes, Inc. to you, subject to your agreeing to the following terms of use (the "Terms"). Read the Terms before using this Site. By using this Site, you signify your assent to the Terms. If you do not agree to these Terms, disconnect from and do not use this Site.

Sizes, Inc. may modify the Terms from time to time, and such modifications shall be effective immediately upon posting of the modified Terms on the Site. You agree to review the Terms periodically to be aware of such modifications and your continued access or use of the Site shall be deemed your conclusive acceptance of the modified Terms.

This version of the Terms is dated: 4 July 2019.

1. The Site and all elements thereof are provided on an "as is" basis without warranty of any kind, express or implied. Sizes, Inc. disclaims all warranties, express or implied, including without limitation, implied warranties of merchantability, fitness for a particular purpose, or non-infringement. Sizes, Inc. does not warrant that the Site will operate or perform in a manner that is uninterrupted or error-free, or that the Site or host server will be maintained free of viruses or other harmful code. Sizes, Inc. makes no warranties that the information presented in the Site is current, up-to-date, or accurate. Some states and jurisdictions do not allow limitations on implied warranties, so the foregoing may not apply to you. The foregoing shall be enforceable to the maximum extent permitted by applicable law.
2. Under no circumstances and regardless of legal theory, whether in tort, contract or otherwise, will Sizes, Inc. be liable to you or any other party for an indirect, special, incidental, reliance, or consequential damages, however caused, and regardless of the character, including without limitation, any damages relating to lost data, computer failure or malfunctioning, or otherwise. Some states and jurisdictions do not allow the limitation of liability for consequential or indirect damages, so the foregoing limitation may not apply to you. The foregoing shall be enforceable to the maximum extent permitted by applicable law. You agree to this allocation of risk in relation to your use of the Site.
3. The Site is presented by Sizes, Inc. from within the United States of America, and Sizes, Inc. makes no representation that materials in the Site are appropriate or available for use in locations outside the United States. Neither the Site, nor any underlying information or technology may be downloaded or otherwise exported or reexported into, or to a national or resident of, any country to which the United States has embargoed goods (for example, Cuba, Iran, Iraq, Libya, North Korea, Sudan, Syria) or to anyone on the U.S. Treasury Department's list of Specially Designated Nations or the U.S. Commerce Department's Table of Denial Orders. By downloading or using any element of the Site, you are agreeing to the foregoing and you are certifying that you are not located in, under the control of, or a national or resident of any such country or on any such list. In

addition, you are responsible for complying with any and all local laws in your jurisdiction which may affect your right to use the Site.

4. You grant to Sizes, Inc. a non-exclusive, royalty-free, worldwide, perpetual license to reproduce, distribute, transmit, create derivative works of, publicly display and publicly perform any materials and other information you submit to the Site, or submit by email or other means of transmission, and you grant to Sizes, Inc. the right to identify you as the source of such materials or information, unless you have specifically requested in a written notice to us not to be identified as the source.
5. Crawling the Site is allowed if done in accordance with the provisions of our robots.txt file, but scraping the Site is prohibited.
6. This agreement shall be governed by and construed in accordance with the laws of the State of California applicable to agreements made and to be performed in California. You agree that any legal action or proceeding between you and Sizes, Inc. for any purpose concerning these Terms or the parties' obligations hereunder shall be brought exclusively in a state or federal court of competent jurisdiction sitting in California. If any provision of this agreement shall be unlawful, void, or for any reason unenforceable, then that provision shall be deemed severable from this agreement and shall not effect the validity and enforceability of any remaining provisions. This is the entire agreement between the parties relating to the subject matter herein and shall not be modified except in writing, signed by both parties.
7. This agreement is effective until terminated by either party. You may terminate this agreement at any time by destroying all materials obtained from this Site and all copies thereof, whether made under the terms of this agreement or otherwise. This agreement will terminate immediately without notice from Sizes, Inc. if in Sizes, Inc.'s sole discretion you fail to comply with any term or provision of this agreement. Upon termination, you must destroy all materials obtained from this Site and all copies thereof, whether made under the terms of this agreement or otherwise.

Index

- 1/16, 53
- 1/160, 53
- 1/2, 53
- 1/20, 53
- 1/32, 53
- 1/4, 53
- 1/40, 53
- 1/64, 53
- 1/8, 53
- 1/80, 53
- 11/1280, 53
- 11/32, 53
- 11/320, 53
- 11/64, 53
- 11/640, 53
- 13/1280, 53
- 13/2560, 53
- 13/32, 53
- 13/64, 53
- 15/2560, 53
- 15/32, 53
- 15/64, 53
- 17/2560, 53
- 17/64, 53
- 25/5120, 53
- 27/5120, 53
- 3/16, 53
- 3/160, 53
- 3/32, 53
- 3/320, 53
- 3/640, 53
- 3/8, 53
- 3/80, 53
- 5/16, 53
- 5/32, 53
- 5/64, 53
- 5/640, 53
- 7/1280, 53
- 7/160, 53
- 7/17, 53
- 7/32, 53
- 7/320, 53
- 7/64, 53
- 7/640, 53
- 9/128, 53
- 9/1280, 53
- 9/160, 53
- 9/32, 53
- 9/320, 53
- 9/64, 53
- 9/640, 53
- A Handbook of Practical Telegraphy, 15
- A. Roebling's Sons Company, 5
- Acceptable Ads, 56
- ad-blocker, 56
- AdBlockPlus, 56
- AdSense, 56
- aluminum cable, 30, 32
- American, 35–38
- American Steel and Wire Co., 35–38
- American, 6–10, 39
- American Standard twist drills, 5
- American Steel and Wire Co., 5, 45
- American Steel and Wire Gauge, 3, 5
- American Wire Gauge, 3, 7
- American wire manufacturers, 6
- American Wire Wire, 7
- Americans, 19, 29
- analytics program, 56
- analytics service, 56
- anonymous data, 55, 56
- Asia Minor, 19, 29
- Association of Brass Wire and Sheet Manufacturers, 6
- ASTM Standard B 258-02, 7
- Austria, 19, 29
- AWG, 7, 32
- AWG-sized cable, 32
- B. & S., 3
- B. & S. G., 6
- B. B. wire, 34
- B. G., 17
- B.W.G., 15–17
- Baidu, 55
- baked, 33
- baker, 33
- batted, 34
- Bedson's continuous galvanizing process, 34

- Belgium, 19, 29
- Bell Wire, 16
- bench hardened wire, 34
- Bing, 55
- Birmingham, 35–38
- Birmingham Wire Gauge (Stubs'), 15
- Birmingham, 11–13, 41
- Birmingham Exchange, 16
- Birmingham Gauge, 16, 17
- Birmingham or Stubs' Wire Gauge, 14
- Birmingham system, 6
- Birmingham Wire Gauge, 11, 15–17
- Birmingham wire gauge, 16, 19, 29
- Birmingham Wire Gauges, 15
- Birmingham Wire-gauge, 6
- Birmingham wire-gauge, 6, 16, 19, 29
- Birmingham, England, 6
- Birmingham, Stubs' Iron Wire Gauge, 3
- block, 33
- Board of Trade, 17
- Board of Trade.
- 12th Annual Report to Parliament on Standard Weights and Measures, 16
- boldface emphases, 33
- bright annealed wire, 34
- bright finished, 33
- Britain, 4, 16
- British Association, 16
- British colonies, 19, 29
- British Standard Wire Gage, 3
- British Standard Wire Gauge, 30
- Brown & Sharp Wire Gauge, 6–10
- Brown & Sharpe, 6, 53
- Brown & Sharpe Catalog No. 29, 53
- Brown & Sharpe Company, 6
- Brown & Sharpe Wire Gauge, 3, 35–39
- Brown and Sharpe, 19, 29
- Brown and Sharpe's American Gauge, 17
- bundles, 33
- BWG, 15
- C. Holtzapffe, 12
- C. Holtzapffel, 12, 15
- C.V. Walker, 18
- CCPA, 55
- Charles Scribner's Sons, 15
- Charles T. Chester, 15
- Chester, 15
- Circular of the Bureau of Standards, 15
- Cl. de Laharpe, 20, 25, 27
- Clark, 17
- Cocker's, 17
- Cocker's Wire Gauge, 5
- cold drawing, 33
- Cologne, 19, 29
- Conductors for Electrical Distribution. Their Materials and Manufacture, 6
- cookie, 55
- cookies, 56
- copper AWG, 32
- copper coating, 33
- copper SWG cable, 30
- Copper Wire Tables, 15
- coppered, 33
- Culley, 16
- Delaware corporation, 56
- Denmark, 19, 29
- Department of Telegraphs for India, 15
- Dept. of Commerce and Labor, 15
- die plate, 33
- draw bench, 33
- draw plate, 33
- drawing, 33
- dry drawing, 33
- DuckDuckGo, 55
- E. B. B. wire, 34
- Edison Electrical Light Company, 4
- Edison Standard Wire Gauge, 4
- Engineering, 17
- England, 19, 29
- English, 19, 29
- English wire gauges, 19, 29
- Europe, 19, 29
- Felten & Guillaume, 19, 29
- finishing blocks, 33
- four-sided charcoal wire, 34
- France, 19, 29
- Frederick A. C. Perrine, 6
- French, 19, 29
- French gauge, 19, 29
- French Wire, 3
- Galvanized Armor Wire, 17
- Galvanized Telegraph and Telephone Wire, 17

- Galvanized wire, 34
- galvanizing pan, 34
- GDPR, 55
- German, 19, 29
- Germany, 19, 29
- Glasgow Practical Mechanic and Engineers' Magazine, 15
- Google, 55, 56
- Google Adsense, 56
- Google Analytics, 56
- Google Analytics Advertising Features, 56
- Great Britain, 19, 29
- Greece, 19, 29
- grippers, 33
- Gun screw wire, 34
- H. Mallock, 16
- Hardware Tables, Formulae and Recipes..., 23
- holes, 33
- Holtzapffel, 15
- Holtzapffel's, 15
- Holtzapfelt, 12
- Hugh P. Tiemann, 3, 34
- Hugh Tiemann, 33
- Idaho, 55
- Imperial Wire Gauge, 35–38
- Imperial Wire Gauge, 16, 17, 47
- Improved steel wire, 34
- Iron and Steel. A Pocket Encyclopedia, 34
- Iron Masters' Association, 17
- Ironmonger, 23
- Italy, 19, 29
- jauge "carcasse", 19, 29
- jauge "japy", 19, 29
- Jauge Carcasse, 3
- Jauge Carcasse or du Commerce, 27
- Jauge carcasse or du Commerce, 28
- Jauge de Limoges, 3, 25–27
- Jauge de Paris, 3
- jauge de Paris, 19, 29
- Jauge de Paris 1857, 20
- Jauge Japy, 4, 23, 24
- javascript, 56
- JDP, 21
- John A. Roebling's Sons Company, 3, 6, 17
- Joshua Rose, 15
- Journal of the Franklin Institute, 15
- Journal of the Society of Telegraph Engineers, 18
- kill, 33
- lacquer, 33
- lacquered, 33
- Lancashire gauge, 4
- Latimer Clark, 13, 15, 18
- lees coating, 33
- lees liquor, 33
- lime bath, 33
- liming, 33
- liquor-bright process, 33
- London Gage, 4
- London gage, 4
- London: The Ironmonger, 23
- Lufkin Precision Tools, Catalog No. 7, 53
- M. Welles, 19, 29
- manufactured-iron trade, 17
- Market Wire Gauge, 4, 5
- McGraw-Hill Book Company, 34
- metric, 30
- metric cable, 32
- metric conductor, 32
- metric system, 19, 29
- metric value, 30, 32
- metric-sized, 32
- metric-sized cable, 30
- metrically-sized, 30
- micrometer, 19, 29
- Middle Ages, 21
- millimetre gauge, 19, 29
- millimetre wire gauge, 19, 29
- Modern Machine-Shop Practice, 15
- Morse Twist Drill Gauge, 4
- Mr. Culley, 16
- Mr. Hatton, 17
- Mr. L. Clark, 17
- Mr. Latimer Clark, 16
- Multiple drawing, 33
- Müllheim, 19, 29
- nippers, 33
- nipping blocks, 33
- Norway, 19, 29
- Notes & Formules de L'Ingénieur et du Constructeur-Mécanicien, 20

- Notes & Formules de L'Ingénieur et du Constructeur-Mécanicien, 25, 27
- Old English Wire Gage, 4
- Old English Wire-gauge, 6
- On a New Telegraph Wire Gauge, 16
- On the Birmingham Wire Gauge, 18
- On the Unit of the Birmingham Wire Gauge, 18
- Paris Gauge, 21
- Paris gauge, 21
- Paris: E. Bernard & Cie, 20, 25, 27
- Partridge's gauge, 17
- patented steel wire, 34
- pickling bath, 33
- Plain annealed wire, 34
- Plain drawn wire, 34
- Plow steel wire, 34
- pricking, 33
- R. S. Culley, 13, 15
- ratch, 33
- Report of the Committee of the Society of Telegraph Engineers on the Birmingham Wire Gauge, 17
- Report to the Council of the Society of Telegraph Engineers on the Birmingham Wire Gauge, 18
- rinsing bath, 33
- Robinson's, 17
- Roebling, 35–38
- Roebling, 15, 45
- Roebling Wire Gauge, 4
- Roebling's book, 15
- roughing blocks, 33
- Russia, 19, 29
- rust coating, 33
- Ryland's, 17
- scouring barrel, 34
- screw gauge, 19, 29
- Second Wire Gauge Report, 17
- sinkers, 34
- Sizes.com, 6, 7, 9, 55
- South America, 19, 29
- South Staffordshire Ironmasters' Association, 17
- Spain, 19, 29
- STANDARD GOVERNMENT WIRE, 15
- Standard Inch, 15
- steel wire, 33
- Steel Wire Gauge, 4, 5, 30, 35–38, 51
- straw-tinted, 33
- stringing up, 33
- Stub's Iron Wire Gauge, 5
- Stubbs', 19, 29
- Stubs', 15
- Stubs' Iron Wire, 35–38, 41
- Stubs' Iron Wire Gauge, 15, 17
- Stubs' Steel Wire Gauge, 17, 35–38, 43
- Stubs' Wire Gauge, 11–13
- Stubs's gauge, 17
- Sweden, 19, 29
- SWG, 30
- SWG-sized cable, 30
- Switzerland, 19, 29
- Table Comparing Common Gauges Sizes, 3
- TECHNISSAGE, 21
- Telegraph Wire, 15
- Telegrapher, 15, 16
- The American Wire Gauge, 32
- The Electrical World, 19, 29
- The Electrician and Electrical Engineer, 20, 29
- The English Wire Gauge, with Descriptive Tables and Drawings, 17
- Thomas Hughes, 17
- Tinman's wire, 34
- trackers, 56
- U.S. government specification, 15
- United States, 7, 11, 15, 16, 19, 29
- United States Consular Reports, 17
- United States of America, 19, 29, 53
- United States Standard Gage, 53
- United States Standard Gauge, 4
- W. H. Preece., 16
- Washburn & Moen, 35–38
- Washburn & Moen, 19, 29, 45
- Washburn & Moen Wire Gauge, 4
- Washburn and Moen Gauge, 5
- Washburn and Moen Manufacturing Company, 5
- water coating, 33
- Waterbury Co., 35–38
- Waterbury Co., 51
- Watkins', 17
- Welles, 20, 29
- Westphalian wire gauge, 19, 29

wet drawing, 33
Whitworth's, 35–38
Whitworth's, 49
Whitworth's Wire Gauge, 4
Wilson King, 17
wipers, 34
wire, 33
Wire in Electrical Construction, 3, 6, 17
Wire in Electrical Construction., 5
wire rods, 33
WWW.Sizes.com/materls, 6
Wynn's, 17

Yahoo, 55
Yandex, 55